

<b>PROJECT:</b>	<b>95th St. Streetscape Improvements, Town of Surfside, FL</b>	<b>DATE:</b>
<b>BIDDER'S NAME:</b>		

Contractor is responsible for verifying quantities and bringing discrepancies to the attention of landscape architect for clarification. Any discrepancies in quantities or units discovered or disclosed after award will be priced upon the unit price stated below.

SCHEDULE OF PRICES BID					
PAY ITEM No.	APPROXIMATE QUANTITY & UNITS		DESCRIPTION	UNIT PRICE	TOTAL EXTENDED PRICE
<b>CIVIL ENGINEERING + PLUMBING</b>					
<b>AREA "A" 95th Street Right-of-Way</b>					
1	1	LS	<b>General:</b> This item includes all Permitting Fees, Insurance and Bonds. Including NPDES, FDOT MOT, FDOT Construction Agreement Permits.	\$	\$
2	1	LS	<b>Mobilization:</b> All work required to mobilize equipment and personnel to begin work at project site. This line item also includes demobilization of equipment and personnel at completion of job.	\$	\$
3	1	LS	<b>Demolition:</b> Furnish all, equipment, machinery, tools, apparatus, means of transportation and labor necessary for and complete the project in full and complete accordance with the shown, noted, described and reasonably intended requirements of the plans. This item includes but is not limited to removal of existing asphalt paving, sidewalks, curbing as noted, and fixtures and excavation of proposed and existing planters.	\$	\$
4	1	LS	<b>Clearing and grubbing:</b> All work furnish and install required to clear site of existing sod, remove trees noted on plans and disposal of all material.	\$	\$
5	1	LS	<b>Fill:</b> Furnish and install fill in accordance with plans. Work shall include the necessary grading to achieve the desired site grading. Fill shall meet Florida Department of Environmental Protection requirements.	\$	\$
6	1	LS	<b>Excavation:</b> Furnish and install excavation in accordance with plans and specifications. Work shall include the movement of material onsite to achieve the desired site grading. Work shall also include all costs to haul, and dispose of all deleterious excavated material not suitable for use onsite.	\$	\$
7	1	LS	<b>Grading:</b> All work required to grade site to elevations depicted on plans for soft and hard areas. This work shall include surveying, staking and any activity and equipment necessary to deliver a graded site.	\$	\$
8	1	LS	<b>Drainage:</b> <i>Furnish and install all materials, equipment, machinery, tools, apparatus, means of transportation and labor necessary for and complete the project in full and complete accordance with the shown, noted, described and reasonably intended requirements of the plans and specifications. This item includes but is not limited to drainage structures, pipes, under drain, <b>exfiltration trench</b>, and coring of existing structure.</i>	\$	\$
9	1	LS	<b>Water:</b> Furnish and install all materials, equipment, machinery, tools, apparatus, means of transportation and labor necessary for and complete the project in full and complete accordance with the shown, noted, described and reasonably intended requirements of the plans and specifications. This item includes but is not limited to irrigation water meter, irrigation backflow preventer, irrigation service and shower as per the plans.	\$	\$
10	1	LS	<b>Signage:</b> Furnish and install all materials, equipment, machinery, tools, apparatus, means of transportation and labor necessary for and complete the project in full and complete accordance with the shown, noted, described and reasonably intended requirements of the plans. This item includes but is not limited to one Stop Sign and replacement of any existing signs that are disturbed in any way shape or form.	\$	\$

PAY ITEM No.	APPROXIMATE QUANTITY & UNITS		DESCRIPTION	UNIT PRICE	TOTAL EXTENDED PRICE
<b>AREA "B" 95th on Ocean Adjacent Property</b>					
11	1	LS	<b>General:</b> This item includes all Permitting Fees, Insurance and Bonds. Including NPDES, FDOT MOT, FDOT Construction Agreement Permits.	\$	\$
12	1	LS	<b>Mobilization:</b> All work required to mobilize equipment and personnel to begin work at project site. This line item also includes demobilization of equipment and personnel at completion of job.	\$	\$
13	1	LS	<b>Demolition:</b> Furnish all, equipment, machinery, tools, apparatus, means of transportation and labor necessary for and complete the project in full and complete accordance with the shown, noted, described and reasonably intended requirements of the plans and specifications. This item includes but is not limited to removal of existing asphalt paving, sidewalks, curbing as noted, and fixtures.	\$	\$
14	1	LS	<b>Clearing and grubbing:</b> All work furnish and install required to clear site of existing sod, remove trees noted on plans and disposal of all material.	\$	\$
15	1	LS	<b>Fill:</b> Furnish and install fill in accordance with plans and specifications. Work shall include the necessary grading to achieve the desired site grading. Fill shall meet Florida Department of Environmental Protection requirements.	\$	\$
16	1	LS	<b>Excavation:</b> Furnish and install excavation in accordance with plans and specifications. Work shall include the movement of material onsite to achieve the desired site grading. Work shall also include all costs to haul, and dispose of all deleterious excavated material not suitable for use onsite.	\$	\$
17	1	LS	<b>Grading:</b> All work required to grade site to elevations depicted on plans for soft and hard areas. This work shall include surveying, staking and any activity and equipment necessary to deliver a graded site.	\$	\$
<b>SITE CONCRETE, PAVING &amp; SURFACING</b>					
<b>AREA "A" 95th Street Right-of-Way</b>					
18	11,000	SF	12" Compacted Subgrade	\$	\$
19	6,000	SF	8" Compacted Lime Rock Base	\$	\$
20	4,810	SF	6" Compacted Lime Rock Base	\$	\$
21	600	LF	4" Lime Rock Curb Pad	\$	\$
22	5	LF	Furnish and install: Color Concrete "F" Curb at drainage structure (corner of 95th and A1A)	\$	\$
23	32	LF	Furnish and install: 12" Concrete Band at cross walk	\$	\$
24	20	LF	Furnish and install: Colored Concrete Sidewalk (Width Varies Per Plan) at corner of 95th and A1A.	\$	\$
25	10,842	SF	Furnish and install: 6" x 6" HT Concrete Pavers x 60MM, 45° Stack Bond Squares, Color: see Hardscape Finish Schedule items "A,B,C, and D"	\$	\$
26	72	CY	2" Compacted Construction Sand Base	\$	\$
27	26	SF	Furnish and install: 6" x 6" HT Concrete Pavers x 60MM, 90° Stack Bond Squares, Color:white with reflectivity	\$	\$
28	1,023	LF	Furnish and install: 4" x 8" PS Concrete Pavers x 60MM, 8" Soldier Course, Color: White, see Hardscape Finish Schedule item "E"	\$	\$
29	25	SF	Furnish and install: 4" x 8" PS Concrete Pavers x 60MM, 90° Stack Bond Rectangles, Color: White with Reflectivity, see Hardscape Finish Schedule item "F" (Stop Bar)	\$	\$

PAY ITEM No.	APPROXIMATE QUANTITY & UNITS		DESCRIPTION	UNIT PRICE	TOTAL EXTENDED PRICE
30	53	SF	Furnish and install: 4" x 8" ADA Concrete Pavers x 60MM, 90 Stack Bond Rectangles, Color: see Hardscape Finish Schedule item "F1"	\$	\$
31	1	LS	Furnish and install: Concrete Sidewalk and Stair w/welded wire mesh reinforcement, medium broom finish, 6" tooled continuous concrete edge along all edges, including all structural design, ADA compliant Stainless Steel hand railings and 8"H x 6"W Color Concrete Cheek wall, see Hardscape Finish Schedule item "O"	\$	\$
32	340	LF	Furnish and install: 6" Color Concrete "D" Curb (Planters), see Hardscape Finish Schedule item "K"	\$	\$
33	230	LF	Furnish and install: 2'-0" Color Concrete Valley Gutter, see Hardscape Finish Schedule item "L"	\$	\$
34	30	LF	Furnish and install: 2'-0" Color Concrete Ribbon Curb, see Hardscape Finish Schedule item "M"	\$	\$
35	383	LF	Furnish and install: 6" Color Concrete Band, see Hardscape Finish Schedule item "N"	\$	\$
36	1	LS	Furnish and install 1' X 2' X 30' continuous concrete reinforced bollard footing, see Hardscape Details.	\$	\$
37	1	LS	Furnish and install a concrete reinforced bike rack footing, per Hardscape Details.	\$	\$

**AREA "B" 95th on Ocean Adjacent Property**

38	400	SF	Furnish and install: Concrete Sidewalk w/welded wire mesh reinforcement, medium broom finish, 6" tooled continuous concrete edge along all edges, see Hardscape Finish Schedule item "O1"	\$	\$
----	-----	----	---	----	----

**SITE FURNITURE**

**AREA "A" 95th Street Right-of-Way**

39	2	EA	<b>Litter Receptacles:</b> Stainless Steel, Side Opening, 30 Gal. Model Lakeside-Grass Furnish and install Litter Receptacle and all costs associated with material handling, storage and delivery, shall meet or exceed the specifications as indicated in the site furniture schedule and plans. Item includes all Litter Receptacles within project area, see Hardscape Finish Schedule item "G"	\$	\$
40	3	EA	<b>Bike Racks:</b> Stainless Steel Model Ring / Embedded or approved equal. Furnish and install bike rack and all cost associated with material handling, storage and delivery, shall meet or exceed the specifications as indicated in the site furniture schedule and plans. Item includes all Bike Racks within project area, see Hardscape Finish Schedule item "H"	\$	\$
41	6	EA	<b>Bench:</b> Reinforced Cast Stone Glass Lenses Bench, Model Escofet - Villet / Embedded or approved equal. Furnish and install bench and all costs associated with material handling, storage and delivery, shall meet or exceed the specifications as indicated in the site furniture schedule and plans. Item includes all Benches within project area see Hardscape Finish Schedule item "I"	\$	\$
42	1	EA	<b>Beach Shower:</b> Four heads and one foot spray head, Model Stainless Steel 590SMSS or approved equal. Furnish and install Beach Shower and all costs associated with material handling, storage and delivery, shall meet or exceed the specifications as indicated in the site furniture schedule and plans. Item includes Beach Shower within project area see Hardscape Finish Schedule item "J"	\$	\$

PAY ITEM No.	APPROXIMATE QUANTITY & UNITS		DESCRIPTION	UNIT PRICE	TOTAL EXTENDED PRICE
<b>LANDSCAPE PLANTS ( trees, palms, shrubs, groundcover and sod )</b>					
<b>AREA "A" 95th Street Right-of-Way</b>					
43	2	EA	<b>Relocate Phoenix dactylifera 'Medjool'</b> , transplant and install plants including planting soil, fertilizer, herbicide, pre-emergence herbicide, seed and staking/guying.	\$	\$
44	9	EA	<b>Relocate Sabal palmetto</b> , transplant and install plants including planting soil, fertilizer, herbicide, preemergence herbicide, seed and staking/guying.	\$	\$
45	13	EA	<b>Phoenix dactylifera 'Medjool'</b> , furnish and install trees including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, plans and specs.	\$	\$
46	230	EA	<b>Uniola paniculata</b> , furnish and install shrubs and groundcovers including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, plans and specs.	\$	\$
47	683	EA	<b>Helianthus debilis</b> , furnish and install shrubs and groundcovers including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, plans and specs.	\$	\$
48	190	EA	<b>Spartina bakeri</b> , furnish and install shrubs and groundcovers including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, plans and specs.	\$	\$
49	1	EA	<b>Zamia furfuracea (45 gal.)</b> , furnish and install shrubs and groundcovers including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, plans and specs.	\$	\$
50	2	EA	<b>Zamia furfuracea (15 gal.)</b> , furnish and install shrubs and groundcovers including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, plans and specs.	\$	\$
51	240	SF	<b>Paspalum 'Aloha Seashore'</b> , furnish and install sod including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, plans and specs.	\$	\$
52	66	QY	Furnish and install soil mixture (3; LL-3) in planters; both existing and proposed.	\$	\$
53	22	QY	Furnish and install organic mulch such as Flora Mulch or approved equal. Red mulch or Cypress are strictly prohibited.	\$	\$
<b>AREA "B" 95th on Ocean Adjacent Property</b>					
54	6	EA	<b>Relocate Sabal palmetto</b> , transplant and install plants including planting soil, fertilizer, herbicide, preemergence herbicide, seed and guying/staking.	\$	\$
55	10	EA	<b>Sabal palmetto</b> , furnish and install trees including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, guying/staking, plans and specs.	\$	\$
56	4	EA	<b>Uniola paniculata</b> , furnish and install shrubs and groundcovers including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, plans and specs.	\$	\$
57	120	EA	<b>Helianthus debilis</b> , furnish and install shrubs and groundcovers including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, plans and specs.	\$	\$
58	350	EA	<b>Spartina bakeri</b> , furnish and install shrubs and groundcovers including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, plans and specs.	\$	\$
59	1,760	SF	<b>Paspalum 'Aloha Seashore'</b> , furnish and install sod including planting soil, fertilizer, herbicide, preemergence herbicide, seed, mulch and meet or exceed the size as indicated in the plant list, plans and specs.	\$	\$
60	20	CY	Furnish and install organic mulch such as Flora Mulch or approved equal. Red mulch or Cypress are strictly prohibited.	\$	\$

PAY ITEM No.	APPROXIMATE QUANTITY & UNITS	DESCRIPTION	UNIT PRICE	TOTAL EXTENDED PRICE
<b>IRRIGATION</b>				
<b>AREA "A" 95th Street Right-of-Way</b>				
61	1	EA	Rain Bird Stream Bubbler PA-8S-5H-B	\$
62	3	EA	Rain Bird Stream Bubbler PA-8S-5CST-B	\$
63	4	EA	Rain Bird 4" Pop-up sprinkler / spray nozzle 1804-PRS-10T	\$
64	7	EA	Rain Bird 4" Pop-up sprinkler / spray nozzle 1804-PRS-10H	\$
65	2	EA	Rain Bird 12" Pop-up sprinkler / spray nozzle 1812-PRS-10V	\$
66	6	EA	Rain Bird 12" Pop-up sprinkler / spray nozzle 1812-PRS-10Q	\$
67	4	EA	Rain Bird 12" Pop-up sprinkler / spray nozzle 1812-PRS-10T	\$
68	16	EA	Rain Bird 12" Pop-up sprinkler / spray nozzle 1812-PRS-10H	\$
69	4	EA	Rain Bird 12" Pop-up sprinkler / spray nozzle 1812-PRS-10F	\$
70	3	EA	Rain Bird 12" Pop-up sprinkler / spray nozzle 1812-PRS-15RCS	\$
71	1	EA	Rain Bird 12" Pop-up sprinkler / spray nozzle 1812-PRS-15LCS	\$
72	1	EA	Rain Bird 12" Pop-up sprinkler / spray nozzle 1812-PRS-15SST	\$
73	500	LF	Techline Dripperline TLCV912	\$
74	8	EA	Techline Flush Valve TLFV	\$
75	2	EA	Rain Bird 1" Solenoid Valve 100PEB	\$
76	1	EA	Rain Bird Zone Control Kit XCFZ-100-PRF	\$
77	1	EA	Rain Bird Auto Controller ESP-4M	\$
78	1	EA	Rain Bird Rain Sensor RSD-BEX	\$
79	1	EA	Febco Pressure Vacuum Breaker 765 (1 1/2")	\$
80	1	EA	Gate Valve (to line size)	\$
81	12	EA	Valve Box	\$
82	1	EA	City Water Meter	\$
83	1	LS	Furnish and install all (SCH 40 Galvanized steel pipes, SCH 40 PVC Main line, Sleeves, Laterals, Supply headers, Discharge header, Sprinkler riser, PVC Fitting, Wire conduit, soil staples, accessories, electric wire, etc.) in order to complete the irrigation System.	\$
<b>AREA "B" 95th on Ocean Adjacent Property</b>				
84	1	EA	Rain Bird 12" Pop-up sprinkler / spray nozzle 1812-PRS-10Q	\$
85	11	EA	Rain Bird 12" Pop-up sprinkler / spray nozzle 1812-PRS-10H	\$
86	2	EA	Rain Bird 12" Pop-up sprinkler / spray nozzle 1812-PRS-10F	\$
87	1	EA	Rain Bird 4" Pop-up sprinkler / rotary nozzle 1804-24Q	\$
88	5	EA	Rain Bird 4" Pop-up sprinkler / rotary nozzle 1804-24H	\$
89	1	EA	Rain Bird 4" Pop-up sprinkler / rotary nozzle 1804-24F	\$
90	3	EA	Rain Bird 12" Pop-up sprinkler / rotary nozzle 1812-24Q	\$
91	3	EA	Rain Bird 12" Pop-up sprinkler / rotary nozzle 1812-24H	\$
92	2	EA	Rain Bird 12" Pop-up sprinkler / rotary nozzle 1812-24F	\$
93	3	EA	Rain Bird 1" Solenoid Valve 100 PEB	\$
94	1	EA	Gate Valve (to line size)	\$
95	4	EA	Valve Box	\$
96	1	LS	Furnish and install all (SCH 40 Galvanized steel pipes, SCH 40 PVC Main line, Sleeves, Laterals, Supply headers, Discharge header, Sprinkler riser, PVC Fitting, Wire conduit, soil staples, accessories, electric wire, etc.) for a complete working irrigation System in place.	\$

PAY ITEM No.	APPROXIMATE QUANTITY & UNITS		DESCRIPTION	UNIT PRICE	TOTAL EXTENDED PRICE
<b>ELECTRICAL</b>					
<b>AREA "A" 95th Street Right-of-Way</b>					
97	250	LF	<b>FPL Connection Point</b>	\$	\$
98	3	EA	<b>Light Pole</b> , Beacon products luminaire 80W, Amber LED type 3 optics MRDS21/36NB-80/T3/UNV/BB mounted in Ameron Pole Kodiak Model: 10ET18-FBCMLS. Fixtures must include shades as required by Florida Department of Environmental Protection.	\$	\$
99	5	EA	<b>Bollard</b> , Gardco 830 Series LED Concrete Bollard Model # BRM833/36/CWL/LA/360/120-240/BLP	\$	\$
100	1	LS	Furnish and install (lighting pull box, concrete bases, miscellaneous conduit and wiring, installation, grounding, etc.) for a complete working Site Lighting system in place.	\$	\$
101	1	LS	3' X 8' X 3' Stainless Steel Service Point Enclosure, footing and attachment; see hardscape details	\$	\$
102	1	LS	Service Point Riser	\$	\$
<b>TOTAL BASE BID PRICE (In Figures 1 thru 98)</b>				<b>\$</b>	
<b>ADD ALTERNATES</b>					
103	11,963	SF	Substitute the base bid standard colored concrete pavers with custom dark color concrete pavers.	\$	\$
104	53	SF	Substitute the base bid standard colored concrete truncated dome pavers, with custom dark color concrete pavers.	\$	\$
105	2,500	SF	In the driveways for Spiaggia Ocean Building, between the 95th Street southern right-of-way line and the north face of the building, remove existing pavers and replace with same depth pavers, standard color concrete pavers per Item "A" on LH-3.	\$	\$
106	2,500	SF	In the driveways for Spiaggia Ocean Building, between the 95th Street southern right-of-way line and the north face of the building, remove existing pavers and replace with same depth pavers, custom dark color concrete pavers per Item "A" on LH-3.	\$	\$
107	230	LF	Replace existing colored valley gutter on the south side of the right-of-way with the same, in standard grey concrete.	\$	\$
108	110	LF	Replace existing colored Type "D" landscape planter curbs on the southside of the right-of-way with the same, in standard grey concrete.	\$	\$
<b>109</b>	65	LF	<i>Substitute the base bid 3'x10' exfiltration trench with 4'x15' exfiltration trench.</i>	\$	\$
<b>DEDUCT ALTERNATES</b>					
110	265	LF	Substitute the base bid colored concrete valley gutter, Type F' curb and ribbon curb with standard grey concrete.	\$	\$
111	1	LS	Substitute the base bid colored concrete sidewalk, stairs and cheek walls with standard grey concrete.	\$	\$
112	340	LF	Substitute the base bid colored concrete Type "D" curb with standard grey concrete.	\$	\$
113	383	LF	Substitute the base bid 6" colored concrete band with standard grey concrete.	\$	\$
<b>114</b>	1	LS	<i>Subtract all improvements east of the existing sea wall.</i>	\$	\$

<b>ABBREVIATIONS</b>	
AC	Acre
CY	Cubic Yard
EA	Each
LF	Linear Foot
LS	Lump Sum
SF	Square Foot
SY	Square Yard